

Complete package includes:

Kiln-dried and precut log walls, sub-floor, Andersen® 400 Series TW windows, Therma-Tru® doors, loft system, complete roof system, interior framing with T&G pine to finish, solid wood interior doors, locksets, and much more!

www.coventryloghomes.com

OVENTRY LOG HOMES, INC.

108 South Court Street • Woodsville, New Hampshire 03785 1-800-308-7505 | 1-603-747-8177 | info@coventryloghomes.com

ONLY \$1 Shipping Within Eastern Time Zone





Take 10% OFF Any Other Model Choose Any Style

Live Your Best Life

Unlimited Technical Support • Three Sets of Construction Plans

Floor SYSTEM

- Girder materials
- Perimeter box 2x10
- Floor joists 2x10
- Sub floor 3/4' engineered sub-floor sheathing T&G
- 1" T&G pine floor (1st floor)

Log Wall SYSTEM

- Solid 6x8 "D" logs
- Pre-cut walls & gables
- Splines
- Caulking & foam gasket
- Corner sealant (spray foam)
- 11" Screw Fasteners

Roof SYSTEM

- Solid 4x8 beam rafters
- 1" T&G pine ceiling boards
- Tie beams as needed
- Soffit material
- Facia material
- All the Tri-flex membrane
- 2" Rigid insulation (3 Layers)
- Roof strapping
- Metal roofing

Loft SYSTEM

- Exposed 4x8 loft joists
- 2" T&G subfloor

Porch SYSTEM

- Perimeter box 2x6 PT
- Floor joists 2x6 PT
- Deck floor 5/4x6 PT
- Railing material PT
- 6x6 posts

Windows SYSTEM

- Andersen 400 Series Low-E
- insulated glass double hung
- insect screen
- Window jamb
- 1x4 trim

Exterior Doors

- Therma-Tru Smooth Star fiberglass
- Entry door w/locksets
- Door jamb
- 1x4 trim Boards

Interior Walls

- 2x4 shoes and plates
- 2x4 studs
- 1" T&G pine boards for wall covering

Interior Doors

Pine doors with hardware

Miscellaneous

- Construction manual
- Unlimited (800) tech assistance

The Cabin Style utility grade logs are structurally sound, though they may have imperfections in appearance.