FALL 2024 SPECIAL Introducing Barndominium Adirondack Design

Limited Time Offer
No other discounts apply

Order w/20% Deposit Oct. 15, 2024

Take Delivery by December 31, 2024



INTRODUCTORY \$95,000 As shown Adirondack Hybrid Style



28x44 • 1,232 sq ft 3 bedrooms • 2 baths

Complete Package Includes:

Hybrid wall system, sub-floor, Andersen® 400 Series TW windows, Therma-Tru® doors, complete roof system, interior framing, locksets, engineered plans if needed and much more! See complete details at: www.coventryloghomes.com



COVENTRY LOG HOMES, INC.

Call Our Log Home Experts 1-800-308-7505



GET MORE FOR LESS

Unlimited Technical Support • Three Sets of Construction Plans Stamped Engineered Plans If Needed



SUB FLOOR

- Perimeter Box Girder Beam
- Joists 3/4" T&G Engineered Sheathing • Stair Stringers/Treads
- Skirt-board



HYBRID WALL SYSTEM

- 2x6 Traditional Wall Framing 16" O.C.
- Zip System Wall Sheathing Zip Wall Tape
- Pine Board and Batten Siding
- Many Other Exterior Siding Options
- Option for T&G To Finish Walls



DORMER OPTIONS

- Siding Options
- T&G Pine Interior Walls




WINDOWS & DOORS

- Andersen Low-E HP Tilt-Wash 400 Series Windows with Screens Custom Gable Glass per plan
- Therma-Tru Fiberglass Doors All Door Hardware
- Window & Door Jambs
- Interior and Exterior Trim Boards
- Custom Gable Window Options



LOFT OPTIONS

Heavy Timber Joists
Girder
2x6 T&G Subfloor
Round
Railings
Heavy Timber Stairs



PORCH & DECK OPTIONS

• Joists • Flooring • Railings • Exposed Beam Roof



INTERIOR

- Partition Framing
- T&G Pine Ceilings
- Option for Pre-hung Interior
 Doors
 Option for T&G Pine
 Walls
 Locksets



ROOF SYSTEM

- Truss & Purlin Beam System With T&G Pine (Center Area)
- Architectural Shingles
- Designed For Your Snow and Wind Loads
- Rafter Roof Wings With T&G Pine
- Metal Roof Option