

# Hillside Model

**Limited Time Offer**  
No other discounts apply

Order w/20% Deposit by:  
June 30, 2025

Take Delivery by:  
December 31, 2025



photo may vary from actual design



## Tradesman Complete Package

**\$175,000** ..... 6x8 Log

**\$189,000** ..... 8x8 Log

## Craftsman Complete Package

**\$193,000** ..... 6x8 Log

**\$208,000** ..... 8x8 Log



**28x42 • 1820 sq ft**  
3 bedrooms • 2.5 baths

## STYLE DIFFERENCES

*The Tradesman Style* is distinguished by its smooth lines and limited use of exposed beams.

*The Craftsman Style* is distinguished by its use of large exposed beams in the loft and roof areas.

*Package Details on Back*



# COVENTRY LOG HOMES, INC.


108 South Court Street • Woodsville, New Hampshire 03785  
www.coventryloghomes.com • info@coventryloghomes.com

Call Our Log Home Experts  
**1-800-308-7505**






- **Unlimited Technical Support**
- **Three Sets of Construction Plans**
- **Stamped Engineered Plans If Needed**



## SUB FLOOR

Sill Seal • Pressure Treated Sill  
 • Perimeter Box • Girder Beam  
 • Joists • Support Joists • Blocking  
 • 3/4" T&G Engineered Sheathing  
 • Stair Stringers/Treads • Basement  
 Stair Landing • Skirt-board Log  
 Siding




## LOG WALL SYSTEM

Kiln-Dried Logs • Milled Tongue & Groove Sealing  
 System • Precut Log Walls w/Window & Door Openings  
 • Precut Log Corner Systems • Precut Gable Angle Cuts  
 • Graded Logs • Sill Seal • Starter Strip • Caulking  
 • Foam Gasket • Corner Sealant • Pre-cut Splines  
 • Screw Fasteners




## DORMERS

Full Log Or Log Siding with  
 Corner Extension Option  
 • Framing  
 • Sheathing Options  
 • T&G Pine Interior Walls




## WINDOWS & DOORS

Andersen Low-E HP Tilt-Wash 400 Series Windows with  
 Screens • Custom Gable Glass per plan  
 • Therma-Tru Fiberglass Doors • Andersen Patio Door/  
 Glider with Screens • All Door Hardware • Window & Door  
 Jamb • Window/Door Headers • Exterior Trim Boards  
 • Interior Trim Boards




## LOFT

Joists • Ledger • Girder  
 • Sheathing Options • Railings  
 • Stair Stringers • Stair Treads  
 • Tie Beams • Stair Landing  
 • Supports • Blocking



## PORCH & DECK

PT Joists • PT Ledger • PT Double Box • PT Flooring  
 • Railing System Options • Porch & Newell Post Options  
 • Exposed Beam Rafter • T&G Ceiling • Roof Sheathing  
 Options • Rafter Nail • Fascia • Roof Membrane  
 • Architectural Shingles Included (or Metal Roof Option)



## INTERIOR

Studs • Plumbing Wall Framing  
 • Blocking • Plates  
 • Plaster Studs  
 • T&G Pine Walls and Ceiling  
 • Support Posts • Wall Stiffeners  
 • Pre-hung Interior Doors  
 • Locksets



## ROOF SYSTEM

Architectural Shingles Included (or Metal Roof Option)  
 • **Common Materials:** Sheathing Options • Starter & Cap  
 • Roof Membrane • Fascia • T&G Pine Interior Ceiling  
 • Soffit • **Tradesman Roof System:** Rafters • LVL Ridge Beam  
 • Rafter Nail • Exposed Tie Beams • Roof Supports  
 • **Craftsman Roof System:** Arms • Purlins (Precut)  
 • Webbing • Truss Cords • Steel Plates • Strapping