

Spring Savings 2026



Order Early Discounts



ORDER by March 31st - Receive 10% OFF

—No other discounts apply—

Ask your representative for details.

Delivery dates are subject to availability and are on a first-come, first-served basis.

Discounts Apply Only to Price List Dated January 1, 2026 and Quotes After that Date.

*Order deposit is 20% of package price • To qualify for discounts delivery must take place by September 30, 2026

COVENTRY LOG HOMES, INC.

108 South Court Street • Woodsville, New Hampshire 03785 • coventryloghomes.com
info@coventryloghomes.com • 603-747-8177 • 800-308-7505 • Fax: 603-747-3340



- Unlimited Technical Support
- Three Sets of Construction Plans
- Stamped Engineered Plans If Needed

Typical Tradesman & Craftsman Package Contents



SUB FLOOR

- Sill Seal • Pressure Treated Sill
- Perimeter Box • Girder Beam
- Joists • Support Joists • Blocking
- 3/4" T&G Engineered Sheathing
- Stair Stringers/Treads • Basement Stair Landing • Skirt-board Log Siding



LOG WALL SYSTEM

- Kiln-Dried Logs • Milled Tongue & Groove Sealing System • Precut Log Walls w/Window & Door Openings
- Precut Log Corner Systems • Precut Gable Angle Cuts
- Graded Logs • Sill Seal • Starter Strip • Caulking • Foam Gasket • Corner Sealant • Pre-cut Splines • Screw Fasteners • Log Siding for Gables • Framing for Log Sided Gables • T&G Pine for Interior Gables • Zip Wall Sheathing for Log Sided Gables



DORMERS

- Full Log Or Log Siding with Corner Extension Option
- Framing • Zip Sheathing
- T&G Pine Interior Walls




WINDOWS & DOORS

- Andersen Low-E HP Tilt-Wash 400 Series Windows with Screens • Custom Gable Glass per plan
- Thermo-Tru Fiberglass Doors • Andersen Patio Door/Glider with Screens • All Door Hardware • Window & Door Jamb • Window/Door Headers • Exterior Trim Boards
- Interior Trim Boards



LOFT

- Joists • Ledger • Girder
- Zip Sheathing • Railings
- Stair Stringers • Stair Treads
- Tie Beams • Stair Landing
- Supports • Blocking



PORCH & DECK

- PT Joists • PT Ledger • PT Double Box • PT Flooring
- Railing System Options • Porch & Newell Post Options
- Exposed Beam Rafter • T&G Ceiling • Roof Zip Sheathing Options • Rafter Nail • Fascia • Roof Membrane • Architectural Shingles or Metal Roof Option



INTERIOR

- Studs • Plumbing Wall Framing
- Blocking • Plates
- Plaster Studs
- T&G Pine Walls and Ceiling
- Support Posts • Wall Stiffeners
- Pre-hung Interior Doors
- Locksets



ROOF SYSTEM

- Architectural Shingles or Metal Roof Option • **Common Materials:** Sheathing Options • Starter & Cap
- Roof Membrane • Fascia • T&G Pine Interior Ceiling
- Soffit • **Standard Roof System:** Pre-built Trusses • Rafters
- LVL Ridge Beam • Rafter Nail • Exposed Tie Beams • Roof Supports • Rigid Insulation (Cabin Series) **Craftsman Roof System:** Arms • Purlins (Precut) • Webbing • Truss Cords • Steel Plates • Strapping